February 14, 2017	
Accumulator Simulated Load Experiment: EXP-01	
Lafayette College: Electrical and Computer Engineering	
Greg Flynn This document contains information about how to set up an experiment to simulate the operation of the accumulator. A simulated load is used for this acquisition. Both one pack and all four in series are documented here.	
Experiment: EXP-01	
Accumulator Simulated Load	
A a a company data a di la a a d	

## **Table of Contents**

Desired objectives	3
Required Hardware	3
Required Software	3
Hardware Setup	4
Software Setup	6
Data	
Desired dataThévenin Voltage	6 6
Temperature	
Appendix A: Wiring requirements	7

#### **Desired objectives**

This experiment should characterize how the packs perform safely. To achieve this the packs will discharge into a simulated load. This will be done in two steps. The first experiment will verify that an individual pack can deliver the expected current. The second experiment will ensure that all of the packs can work together to ensure that the correct current can be driven into the load at the right voltage.

The nominal voltage of 4 packs in series is 89.6VDC. For one pack it is 22.4V. The maximum current that the packs will be asked to draw is 200A. The maximum anticipated voltage is 106.4VDC. The experiments are designed to ensure that no more than 200 A will be drawn in any circumstance.

To run these test a safety plan must have already been agreed and accepted by the ECE Director of Laboratories.

## **Required Hardware**

- 4 Packs in series
- Simulated load
- Basic GLV safety loop
- PPE per safety plan
- Danger zone per safety plan
- Cables as specified in Appendix A
- Temperature Probe

## **Required Software**

None

## **Hardware Setup**




Figure 1 Single pack connections




Figure 2 Full 4 cell test

Accumulator Simulated Load Experiment: EXP-01

Software Setup N/A					
Data					
Perform	n full stress test and ramp the	desired current up to 200 Amp	os.		
Desired data  It is desired to get for both the single pack and the chain of packs:  • Thévenin voltage  • Temperature of cells					
<b>Thévenin Voltage</b> Check all packs individually from 0 Amps to 200 Amps to be able to characterize the Thévenin equivalent. Add more rows as appropriate					
Pack	Current	Voltage at load			
Check	Check chain of packs from 0 Amps to 200 Amps.				
Curren	t	Voltage at load			
Temperature While testing ensure that no part of the pack gets 40C above ambient temperature.					
Witnes	s/examiner signature	Date	Pass/Fail		

Accumulator Simulated Load Experiment: EXP-01

# **Appendix A: Wiring requirements**

1 2 3 4	WHT BRN RED BLK	SL1 SL2 AIRs+ AIRs-	P1 W6 DT06-4S	Safety Loop 16/4 Cable	P2 DT06-4S	1 2 3 4	WHT BRN RED BLK	SL1 SL2 AIRs+ AIRs-
1 2 3 4	WHT BRN RED BLK	SL1 SL2 AIRs+ AIRs-		Safety Loop Tern 16/1 Cable	ninator	1 2 3 4	Jump   1 and Leave 3 and	2 pin
1	RED	TSV HV	P1 TW1 NLDFT-E-GN-L-S120-M40A	Pack 1 + 2/0 Cable	Bare	1	RED	TSV HV
1	RED	TSV HV	P1 TW2 I	2/0 Cable	Bare	1	RED	TSV HV
1	RED	TSV HV	P1 TW3 NLS-N-BL-S120-M40A	Pack 3 + 2/0 Cable	Bare	1	RED	TSV HV
1	RED	TSV HV	P1 TW4 Pa	ack 1 and 3 - 2/0 Cable	Bare	1	RED	TSV HV
1	RED	TSV HV	P1 TW5 Pa	ack 2 and 4 - 2/0 Cable	Bare	1	RED	TSV HV

Cable	What packs	Total count		
	use it	for full test		
W6	1,2,3,4	4		
W7	1,2,3,4	1		
TW1	1	1		
TW2	2,4	2		
TW3	3	1		
TW4	1,3	2		
TW5	2,4	2		

Accumulator Simulated Load Experiment: EXP-01